

Item No	Description	Supply				Erection				Total Supply + Erection Amount (Rs)
		Qty	Unit	Supply Rate (Rs)	Supply amount (Rs)	Qty	Unit	Erection Rate (Rs)	Erection amount (Rs)	
1.0	Make : Daikin - Model No -FTQ TV16U2 (IDU) /RQ60TV16U2(ODU) : Supply , Erection , testing and commissioning of Split AC of 1.8 Tr, 2 star, non inverter type , cooper condenser , Single phase , 50 HZ with remote and all accessories , complete work (Note -Erection of outdoor unit on provided stand at height up to aproximety 11 feet from ground level)	3	No			3	No			
2.0	Make : Dakin- Model No- FTL50 TV16V2(IDU)/ RL50TV16V2 , Supply , Erection , testing and commissioning of Split AC of 1.5 Tr, 3 star, non invter type, cooper condenser, Single phase , 50 HZ with remote and all accessories complete work (Note -Erection of outdoor unit on provided stand at height up to aproximety 8 feet from ground level)	3	No			3	No			
3.0	Supply and erection of copper soft pipe, Make Imported with following size									
3.01	Supply & erection of additional copper pipes 5/8" for extending indoor to outdoor pipe connection	28	Mtr			28	Mtr			
3.02	Supply & erection of additional copper pipes 1/4" for extending indoor to outdoor pipe connection	48	Mtr			48	Mtr			
3.03	Supply & erection of additional copper pipes 1/2" for extending indoor to outdoor pipe connection	23	Mtr			23	Mtr			
4.0	Insulation to copper soft pipe following pipe with 9mm thickness Make Superlon									
4.0-1	Supply & erection of Superloan Insulation for copper pipes 5/8" for extending indoor to outdoor pipe connection	29	Mtr			29	Mtr			
4.0-2	Supply & erection of Superloan Insulation for copper pipes 1/4" for extending indoor to outdoor pipe connection	49	Mtr			49	Mtr			
4.0-3	Supply & erection of Superloan Insulation for copper pipes 1/2" for extending indoor to outdoor pipe connection	23	Mtr			23	Mtr			
5.00	Supply of industrial Copper Flexible cable 3 Core 4 Sq mm Make Polycab 1100V ISI Mark	65	Mtr			65	Mtr			
6.00	Core cutting work by core cutting drill machine to existing wall complete work									
6.0-1	Core Cutting (Size Ø 3 inch) of length of drill 27"					27	Inch			
6.0-2	Core Cutting (Size Ø 3 inch) of length of drill 14"					14	Inch			
7	Drain Pipe PVC Flexible- 20mm	15	Feet			15	Feet			
9	Supply of anchor fasteneres of Size M-10 x 75 mm for fixing the stand in wall (Note - contractor have to be drill the wall first and than fix the fastener in hole)	20	Nos			20	Nos			
10	Fixing to provided MS stand on wall					2	No			
11	Dismantaling of old split AC indoor unit (Note - Submitted in power House)					5	Nos			
12	Dismantaling of old outdoor unit and window AC (Note - Submitted in power house)					4	Nos			
13	Repairing of wall hole for AC pipe with proper closing by white cement , and water proof damgard	1	Job			1	Job			

For Any details Please Contact at Electrical Section VSI, (020-26902312/314)

Note :1) GST Extra As Applicable

2) Mesurement at actual for final bill

3) Pl send quotation on letar head