



VASANTDADA SUGAR INSTITUTE
MANJARI BK., HAVELI, PUNE- 412307
Phone: 020-26902316/26902286 Fax. 020-26902244
WEBSITE: www.vsisugar.com

CORRIGENDUM FOR DATE EXTENTION TO TENDER NOTICE DATED 28/01/2026

This is to inform all prospective bidders that the last date and time of bid submission for Supply, Installation, Testing & Commissioning of Shade Net (As Per Specifications) Qty. 8 Nos has been extended as below.

Sr. No.	Bid Submission last date and time	Extended bid submission last date
1.	04.02.2026 at 11.59 PM	17.02.2026 at 11.59 PM

DIRECTOR GENERAL



VASANTDADA SUGAR INSTITUTE
MANJARI BK., HAVELI, PUNE- 412307
Phone: 020-26902316/26902286 Fax. 020-26902244
WEBSITE: www.vsisugar.com
e - TENDER NOTICE

E- Tender are invited from reputed firms/Suppliers/Manufacturers for following.

Sr. No.	Item/ Description	Tender Form Fees (Incl.GST)	EMD Amount
1	Supply, Installation, Testing & Commissioning of Shed Net (As Per Specifications) Qty. 8 Nos	6,372/-	90,000/-

Note: for details MKCL website: <https://sugarmart.sets.co.in/>



VASANTDADA SUGAR INSTITUTE
MANJARI BK., HAVELI, PUNE- 412307
Phone: 020-26902316/26902286 Fax. 020-26902244
WEBSITE: www.vsisugar.com
e - TENDER NOTICE

E- Tender are invited from reputed firms/Suppliers/Manufacturers for following.

Sr. No.	Item/ Description	Tender Form Fees (Incl.GST)	EMD Amount
1	Supply, Installation, Testing & Commissioning of Shed Net (As Per Specifications) Qty. 8 Nos	6,372/-	90,000/-

Note: for details MKCL website: <https://sugarmart.sets.co.in/>

1.

1. e- Tender notice can be seen on website www.vsisugar.com <https://sugarmart.sets.co.in>

2. The e-tender submission period is from **28 January 2026 to 04 February 2026**, through the Sugarmart website.

3. e- Tender is to be submitted upto **04/02/2026** with following Documents.

- GST Registration
- Udyog Aadhar Card
- PAN CARD
- Copy of Registration Certificate of Trader /Firm/Organization/Industry
- Previous Work experience certificates

4. Pre bid meeting will be held at Vasantdada Sugar institute, Manjari (Bk), Tal. Haveli, Dist. Pune on 02/02/2026 at 15.00 hrs

5. VSI reserves the rights to reject one or all tenders or any items of the tender without Assigning any reason.

Director General

Tender Terms & Conditions

1. Please quote for the rate including freight, warranty, loading & unloading, installation, commissioning and successful operation and taxes separately.
 2. Offer should be valid for 120 days from the last date of submission of Tender
 3. Demand Drafts of Tender form fee and Earnest money deposit (as mentioned in tender notice) should be of Nationalized/schedule Bank in favor of Vasantdada Sugar Institute, Pune.
 4. Supplier/Agency will have to complete the order/work as per the purchase/work order. If the supplier/agency failed to complete the job/work within 30 days, penalty equal 0.5% of cost of contract value per week will be recovered as liquidated damages.
 5. The Institute is not responsible for any accidents/claims during the transportation/work/installation of the material/equipment.
 6. Supplier/Agency should submit the delivery challan, without delivery challan/invoice unloading will not be allowed.
 7. The Supplier/Agency should give prior intimation before unloading.
 8. No advance payment is allowed.
 9. Earnest money deposit will be forfeited if supplier withdraw his offer or refuse to sign an agreement of supply after opening of offers.
 10. The decision of Director General, Vasantdada Sugar Institute is binding on supplier in respect of the all dispute.
 11. T.D.S. provisions of I.T. Act are applicable, and according T.D.S. at applicable rate would be deducted from bill amount.
 12. Selected Supplier/Agency will have to deposit the security deposit of 4 % of the total order cost and sign an Agreement before placement/receiving of purchase order on non-judicial stamp paper of Rs.500/-.
 13. 100% payment will be made within 15 days after completion of work as per order/specification & submission of satisfactory work completion report of user department within 30 days from the date of receipt of bill.
 14. Security deposit shall remain in the hands and custody of VSI without interest up to warranty period.
 15. If the Supplier/Agency failed to complete the work ordered, the same would be purchased from other agency at the risk & cost of the firm.
-

Technical Specification

- Size: - 20 meter x 6 meter = 120 sq. meter
- Shape: - Tunnel (Grid 6 meter x 4 meter)
- Height: - 4 meter at center & 3 meter at sides
- Orientation: - Preferably North - South gutter direction.
- Gutter slope: - 1.25 to 2% (longitudinal slop 0-25%)
- Gutter material: - 100% leakage proof of galvanized sheet minimum 275 GSM with zinc coating.
- Structural design: - the structure is designed to be enough to with stand wind speed minimum 120 km / hour.
- Structure: - Complete structure made of hot dip galvanized steel tubular pipes with a minimum of 360 GSM (with Zinc coated on continuous procedure to meet the quality requirements or equivalent section confirming)
- Columns: - GI pipe as 48 mm OD x 2 mm thick, hot dip 360 GSM GI.
- Foundation: - GI pipe as 48 mm OD x 2 mm thick.
- Trusses member / Arch's:- 48mm OD with 2mm thickness GI pipe structural members to be fitted in plated nuts, bolts and washers without welding.
- Bottom chord: - 48 mm OD with 2 mm thickness GI pipe.
- Support W member: - 33 mm OD with 2 mm thickness.
- Cross Bracings: - 33 mm OD with 2 mm thickness GI pipe to ground the wind load.
- Top, Side & Bottom Purloins: - GI pipe as 42 mm with 2 mm OD.
- Door:- FRP door with fittings, Door Size 2.5 meter x 2.5 mm
- All nut & bolts must be high tensile strength & hot dip galvanized as per requirement.
- Clamps: - Round & half as per pipe size & tensile strength & hot dip galvanized material.
- Accessories: - As per the requirement.
- Spring insert: - Aluminum profile & zigzag locking spring high carbon steel with spring action wire, galvanized of fix shade net, inset proof net into aluminum / GI profile.
- Foundation material for columns: - Ground with cement concrete mixture of 1:2:3 using telescopic insertion of column.
- Size: - depth not less than 100 cm. 2 ft. x 1 ft.
- Shad net:- UV stabilized mono x mono 50% (115 to 120 GSM), Shading net has to be provide horizontally at gutter height, below the UV sheet inside the green house,
- Top cover 75 % green color , Side cover 50% green color with insect proof net.
- Irrigation System: - Fogging system including PVC pipe & fatting, 2000 liter capacity tank rest on 1 feet height ground structure chamber from ground level, double layer water syntax make tank, mono block pump 2 hp, all necessary connection/piping work must done to ensure water supply from bore well to water storage tanks.

- Fogging system: -

- Main & sub main line PVC 50 mm x 6 kg/ cm sq.

- 16 mm LLDPE lateral line

- 4 Way fogger assembly with HPLPD

- Ball valves (Teflon seal, plain), Flush valves, Air release valves assembly.

- Warranty for 5 years from the date of installation for structure excluding net.
 - 3 years warranty for all material and installation defects on pro rata basis civil works.
 - Internal work: - Bed/bottom layer should be prepared by murum or chuck with compaction.
-